


Station	Fill Area	Cut Area	Fill Volume	Cut Volume	Cumulative Fill Vol	Cumulative Cut Vol
0+50.00	0.00	216.78	0.00	0.00	0.00	0.00
0+54.87	0.00	284.36	0.00	45.20	0.00	45.20
0+64.87	0.00	407.42	0.00	128.11	0.00	173.31
0+74.00	0.00	484.80	0.00	150.76	0.00	324.08
0+75.00	0.00	493.16	0.00	18.19	0.00	342.26
1+00.00	0.00	618.27	0.00	563.81	0.00	906.08
1+24.38	0.00	650.76	0.00	642.97	0.00	1549.05
1+25.00	0.00	649.42	0.00	14.90	0.00	1563.95
1+50.00	0.00	602.00	0.00	579.36	0.00	2143.31
1+75.00	0.00	575.15	0.00	544.98	0.00	2688.29
1+84.12	0.00	548.96	0.00	189.75	0.00	2878.03
2+00.00	0.00	499.66	0.00	285.64	0.00	3163.67
2+25.00	0.00	458.72	0.00	409.72	0.00	3573.39
2+47.23	0.00	386.61	0.00	318.28	0.00	3891.68
2+50.00	0.00	395.10	0.00	48.08	0.00	3939.76
2+61.47	0.00	422.39	0.00	211.04	0.00	4150.80
2+75.00	0.00	374.19	0.00	244.08	0.00	4394.88
2+76.47	0.00	363.91	0.00	20.15	0.00	4415.04
3+00.00	0.00	137.25	0.00	263.32	0.00	4678.36
3+25.00	0.00	139.13	0.00	150.38	0.00	4828.74
3+50.00	0.00	273.67	0.00	227.25	0.00	5055.99
3+56.32	0.00	303.85	0.00	81.31	0.00	5137.30
3+75.00	0.16	301.23	0.05	199.27	0.05	5336.57
4+00.00	2.19	312.31	1.10	269.85	1.15	5606.42
4+25.00	10.71	260.25	6.08	251.96	7.23	5858.38
4+50.00	23.36	222.33	16.10	212.77	23.33	6071.16
4+60.86	25.75	223.84	10.09	85.48	33.42	6156.64
4+75.00	24.01	207.65	13.03	112.96	46.45	6269.60
5+00.00	23.83	158.06	22.15	169.31	68.60	6438.91
5+18.02	29.42	115.62	17.77	91.33	86.37	6530.23

NOTE:  
EARTHWORK NOT CALCULATED AT INTERSECTIONS, DRIVEWAYS, SHOULDER WIDENINGS OR TURNAROUND.

**2/22/2011 WORK-IN-PROGRESS / NOT FOR CONSTRUCTION**

\\users\public\ssc\projects\mannci\dwg\0110021107.dwg

DESIGNED:	SSS						
DRAWN:	SSS						
CHECKED:							
DATE:	__/__/2011						
<table border="1"> <thead> <tr> <th>DATE</th> <th>NO.</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td colspan="3" style="text-align: center;">R E V I S I O N S</td> </tr> </tbody> </table>		DATE	NO.	DESCRIPTION	R E V I S I O N S		
DATE	NO.	DESCRIPTION					
R E V I S I O N S							



**SUMMERSETT CIVIL ENGINEERING**  
6305 Miller Road  
Mount Hood Parkdale, OR 97041-8722  
(541) 352-9313

**PRELIMINARY SECTIONS & EARTHWORK - LOWER ROAD**  
**MANCINI ACCESS ROAD**  
T01N R10E S21 TL107 HOOD RIVER COUNTY, OR

SHEET NO. **3** OF **6**  
JOB NO. 01N10E21107